


# WASHING ACCESSORIES

Increase Your Pressure Washing Speed with Accessories



 **HYDRO TEK**

# ROTARY SURFACE CLEANERS




**Hydro Twisters®** are industrial flat-surface cleaners that connect to a pressure washer and use a spray bar rotating at a high speed within 1" of the ground to clean concrete more consistently than an operator with a wand, with less fatigue, 10-20 times faster, and use less water. Hydro Twister surface cleaners can be used with cold water or up to 250° hot water, on some models, for extra stubborn grease or grime, eliminating the need for soap pretreatment in most applications.

## The Hydro Twister® Advantage...

- Low Profile Deck: Will fit under benches & machinery
- Low Maintenance: Stainless permanently lubricated & sealed bearings
- Stainless Rotary Spray Arms: for durability and rust resistance
- Less Fatigue: Handle is held in place at ideal working angle
- Hose is protected inside stainless steel handle (except ANT1N)
- Rustproof and heavy duty for daily use
- Rear splash guard to keep operator's feet dry (except ANT1N)

- driveways, drive-thrus
- patios, garages
- concrete sidewalks
- school yards
- factory & warehouse
- restroom floors
- food processing floors
- service stations
- concrete parking lots
- pool decks
- sport courts
- roofs & decks
- loading docks
- tile flooring
- stadiums
- marina docks
- moss & mildew removal



The **ANT21** HYDRO TWISTER is small but powerful. With a smaller 20" deck, it is ideal to clean under and around workbenches, bakery racks, and other tight spaces. All stainless, rustproof, construction will keep your surface cleaner working and looking great for years. Model# ANT21

The unique **ANT1N** HYDRO TWISTER has a seamless 20" composite deck, is lightweight and will not become brittle with age. The ANT1N is ideal for lower output pressure washers, too. With casters this surface cleaner is ideal for tile and decks. The casters can be removed for floater style operation on uneven surfaces and roofs. Flip it over for use as an undercarriage washer for trucks, trailers, or sanitizing stadium benches. Model# ANT1N



ANT1N 2-in-1 Flat surface cleaner & Undercarriage washer, gun not included

The **ANT28 Professional** HYDRO TWISTER has a large cleaning path. The all stainless construction outlasts all others in even the harshest of washing conditions. The four casters swivel for free movement while cleaning. The heavy duty skirt protects the spray arm from curb and rock damage and has a rear splash guard to keep operator dry. Model# ANT28





The **Contractor Series** HYDRO TWISTER® is the proven choice for professional surface cleaning...with four tools for your cleaning needs. The **ANT4C** combines a rotary surface cleaner, spot / gum remover, hydro broom, and an edger to create an all-in-one deluxe surface cleaner. The dual trigger guns activate either the rotary spray arm or one of the other three devices. By combining four processes into one unit, you will save time and fatigue when cleaning large expanses of concrete, parking lots or other flat surfaces. The secret that makes the Contractor Hydro Twister so effective is the ideal water spray angles and nozzle heights that optimize cleaning power.

Model# ANT4C



An onboard edging tool cleans close to planters, columns, and walls or use the water broom to rinse a large area



The under-deck spot remover uses a "six-shooter" nozzle to blast away gum or paint.

Caster pivot lock allows the operator to choose to lock casters for use in straight lines or unlock for cleaning side-to-side.



Choose the Hydro Twister with the deck and nozzle size that accommodates your power washer					
	ANT1N	ANT21	ANT28	ANT4C	ANTV5
Max. recommended psi/flow	4000 / 4	5000 / 6	4000 / 5.5	4000 / 5.5	4000 / 5.5
Max. flow (w/larger nozzle)	5	6	10	10	6
Min. recommended psi/flow	2500 / 3		3000 / 5	3000 / 5	3000 / 4.8
Standard nozzles (15°)	2) #2.0		2) #2.7	2) #2.7	2) #2.7
Water temperature	cold to 250°	cold to 210°	cold to 250°	cold to 250°	cold to 200°
Deck size	20"		28"	28"	30" (24.5" cleaning path)
Deck construction	Composite		Stainless with rear splash guard		
Handle/frame construction	Stainless		Stainless, adjustable position handle, trigger gun (dual guns on ANT4C)		
Other features	Able to flip over or use as float style		4) caster wheels with O-ring seals		

## WATER RECOVERY SURFACE CLEANERS



The **Twister Vac** is a unique rotary surface cleaner with wash water recovery capability. Imagine how efficient you will clean without the hassle of having to do a final rinse or containing wastewater runoff. Using a Twister Vac with your existing hot water mobile wash skid, you will be able to clean flat surfaces up to 20,000 sq. ft. per hour, plus recover your wash water all in one simple step when you connect to a Hydro Vacuum® recovery system.

Stainless construction, 30" deck. Requires minimum 100cfm/91"lift vacuum source, 2" vacuum hose, and a pressure washer. Suitable for use on greasy factory floors, concrete parking lots and drive-thru areas, gas stations and garages.  
Model# ANTV5



Also available in a 12" composite deck for tight areas or small touch-ups. (Deck color may vary)  
Model# ANT12



**For additional Mobile Wastewater Solutions, ask your dealer for information on the Hydro Vacuum® product line.**

# HOSE REELS



**Stainless steel for the price of painted steel.**

The Hydro Tek hose reels are made with rust-proof stainless & zinc plated steel to withstand harsh environments.

AR110,  
AR151,  
AR152\*\*



AR100, AR150



AR188

If you are looking for a **wall mount hose reel** or a **base mount reel** for mounting almost anywhere, Hydro Tek universal mount reels are right for you. These reels are shipped fully assembled, ship quick, and are proudly made in the USA

Part #	Temp.	Capacity	psi	Type
<b>AR100</b>	250°F	150' of 3/8"	3500	narrow-base mount, friction brake
<b>AR150</b>	400°F	150' of 3/8"	5000	narrow-base mount, friction brake
<b>AR110</b>	250°F	250' of 3/8"	3500	large-base mount, pop-pin brake
<b>AR151</b>	400°F	250' of 3/8"	5000	large-base mount, pop-pin brake
<b>AR152</b>	cold	150' of 5/8"	inlet	large-base mount, pop-pin brake
<b>AR188</b>	400°F	100' of 3/8"	5000	wall mount to 16" stud width

\*\* AR152 now with 1/2" swivel

## Stacking Hose Reels

Two stainless hose reels attached to a sturdy powder coated steel frame that conveniently bolts down to any flat surface.

Two configurations to choose from: Part# AR325 has reel capacities of 250' x 3/8", 5000psi, 400° paired with a 150' inlet reel.

Part# AR326 has reel capacities of 250' x 3/8", 5000psi, 400° paired with another of the same.

Ships in two boxes, ships quick & made in the USA



Hose & gun  
sold separately



## Need a pivoting hose reel?

Look at the AR425. The stainless reel has a capacity of 150' x 3/8", 5000psi, 400° and is designed to mount on tubing with the enclosed clamp, or can be mounted on a wall. The reel has a friction brake for adjusting the drag depending on your job. It will pivot a full 360 degrees or you can slide the pin to lock the rotation where needed.

Ships fully assembled, ships quick & made in the USA

# HOSES

Smooth rubber pressure washer hose with M22 screw couplings and bend protectors. Max 3000psi and 140°F. For use with homeowner/consumer/light duty pressure washers. 50' x 1/4" Part# DH426



Heavy duty, silicone-free inlet garden hose with heavy duty brass fittings on both ends. 100' x 5/8" Part# AG100




The 3/8" **high pressure hoses** are available in 3000psi, 4000psi, and 5800psi, lengths of 50' or 100' and include bend protectors and couplers.

Part #	Temp.	Length	psi
<b>DH050</b>	250°F	50'	3000
<b>DH095</b>	250°F	100'	3000
<b>DH057</b>	250°F	50'	4000
<b>DH097</b>	250°F	100'	4000
<b>DH060</b>	250°F	50' non-marking	5800
<b>DH098</b>	250°F	100' non-marking	5800

# BULK TANKS

Hydro Tek's custom **bulk water tanks** are made from seamless linear polyethylene. Tanks include a large 10" fill lid. The 200 gallon tank is self supporting, while cages or strapping are recommended on larger tanks to keep shape when full. Tanks are available in black or white. You won't need to create a tie down strap, we've done it already. The Hydro Tek steel hold down straps are fabricated to fit these tanks securely. Simply bolt straps down to your flat trailer. Two straps required per tank.



## TANKS

- Part# WT069, 70g, black (48"x25"x13")
- Part# WT201, 200g, white (48"x29"x34")
- Part# WT202, 200g, black (48"x29"x34")
- Part# WT265, 270g, white (48"x34"x41")
- Part# WT267, 270g, black (48"x34"x41")

## HOLD DOWN STRAPS

- Part# HCS20, for 200g tank, stainless
- Part# HTS03, for 270g tank

# SPOT FREE

The Hydro Tek spot free washers include built-in housings for the DI filters to make it more compact and portable than others on the market. A stainless steel frame encloses and protects the filter housings, pump, and motor. Simply insert a Hydro Tek filter pack to remove the impurities from tap water for a spot free finish without having to dry the surface. Quick read meter monitors the water quality to let you know when it is time to change the filters. System designed to conserve water flow and increase filter life.

### The Hydro Tek Spot Free Advantage...


- Compact integrated filter housing
- On-demand DI water: no more bottle leases, bulky bottle storage, or running out of pre-purchased DI water
- Ideal for auto, RV, boat, bus, truck, or window washing.
- Hydro Tek DI filter packs have a high yield and produce ultra pure water. (Treats up to 1000 gallons to a purity of 5ppm or better in average tests, when inlet TDS is 150ppm or less)



Portable, Gas Powered  
2000psi, 2gpm, 160cc Honda engine  
Stainless hose reel included  
Model# CPD20002HH-DI



Portable, Electric powered  
115V, 1ph, 15amp  
1300psi, 2gpm  
Model# CWD13002E1-DI



DI water filter cart  
Connect this DI cart to your existing cold water power washer (up to 3gpm) for spot free washing or connect to a low pressure hose for low flow, unpressurized spot free rinsing.  
Model# CWD00

*DI filters (part# VFD25) required, NEW for 2014: first set included. Additional spot free washers also available*

# HOT WATER GENERATORS

Do you already own a cold water pressure washer but wish it had hot water? Attach a Hot Link to your existing cold water pressure washer and you have the power of hot water to quickly melt away grease and grime.

The **Hot Link System** allows you the flexibility of using hot water on those stubborn jobs such as grease, gum, or graffiti that require the impact of hot water to get the job done right. It will save you money by getting the job done faster, and you do not have to buy a new pressure washer if you already have a cold water system. Its compact size allows for easy storage when not in use and takes up little room on your truck or trailer.

You can choose from two diesel heated models or a propane heated model.



Diesel heated, electric powered

- 12v DC for remote use, hook to the battery on your pressure washer (requires 14 amp charging system)  
Part# CPHL5DC
- 115v, plugs into any standard 15 amp outlet  
Part# CPHL5E1



Propane heated, no power source needed

The push button igniter with a millivolt system does not need to plug into an outlet or charging circuit. Connect to a propane source and your cold water pressure washer for hot water cleaning.

Part# CPHN5-LP

# SPECIALTY SPRAYING SYSTEMS

The **Low Impact, High Reach Spraying System** is a soft wash system ideal for cleaning surfaces that are not tolerant to the impact of a high pressure washer. Simply drop the chemical hose into your tank of solution, even Chlorine, and you are ready to go. Reach rooftops and walls from the ground up to 40' without the use of ladders saving time and increasing worker's safety. It uses two 6 volt batteries and is compact making this a great addition to your wash rig. Includes 250' hose on stainless reel, trigger gun valve and 24" wand.

Part# AC110



# WANDS & SPECIALTY APPLICATIONS


Heavy duty **spray wands** include insulated lance grips for both protection from heat and comfortable two handed use.



Part# AVW40, 42" stainless steel dual lance wand

Part# AVWA3, 42" stainless steel dual lance wand with gun and coupler

Adjustable pressure at the wand or use for downstream soap applications. Includes soap nozzle



Part# AVGH2, 48" spray wand with coupler and trigger gun



Convenient nozzle storage at your fingertips

Part# AVGH3, 48" spray wand, coupler, trigger gun, nozzle holder




Soft, hog hair **bristle brush on 6' long pole**. (Additional 6' pole sections available)

Part# AVW6B, Wash Brush/Pole

Need to pressure wash up high? Reach it safely from the ground with Hydro Tek's **High Reach Wash Pole**. It offers additional control and rigidity not found with telescopic wands. Uses trigger gun from your wash skid, no need to turn off wash skid or change guns. Our maximum ratings are 4500psi and 250°F (while other brands are rated only to 195°F). The Hydro Tek high reach wash pole includes a comfort brace gun holder, full length jumper hose, three sections of 6' poles, spray head attachment, and also includes shoulder strap (Gun holder will hold Hydro Tek VG200 and Suttner ST1500 trigger guns.)

Part# AVW20, High Reach Wash Pole



No need to turn off power washer to change wands, trigger gun from Hydro Tek washer (or Suttner ST1500 gun), snaps easily into gun bracket.



For removing dirt and grime from underneath a vehicle, reach for a Hydro Tek **undercarriage wand** with casters (#AVUN1). Simply attach the wand to your power washer gun, insert your quick connect nozzle and roll under vehicle. The undercarriage wand is also ideal for cleaning under boat trailers and motor homes. Part# AVUN1



Looking for an industrial **chemical sprayer / tank system**? The Hydro Tek low pressure chemical sprayer runs off a 12v battery or can be wired directly to a Hydro Tek SS, SC, or SCU skid and has lighted on/off switch. The rugged frame can be mounted to your existing flat trailer or truckbed, or factory installed on your new ProTowWash® trailer. Includes 50' braided chemical hose, spray wand and 40 gallon chemical tank. Part# AC440



To blast off paint, rust, scale, or graffiti try **wet sandblasting**. The Wet Sandblast nozzle draws sand or even baking soda into the water stream. The standard sandblast assembly features an industrial sand blast head, 50' crushproof PVC sand hose, and a sand probe that will draw directly out of a bag or pail (#ASB55 has 5.5 nozzle size, other sizes available). Baking soda can be used for more delicate jobs such as pool tile cleaning and other sensitive surfaces.

# WATER & FLOOD RECOVERY VACUUMS



Capture and transfer up to 3000 gallons of water per hour with the compact RPV vacuum system. Features a powerful, industrial 2-stage vacuum motor. A heavy duty, stainless steel pump transfers wastewater up to 100' away while vacuuming continues...no need to stop and dump the collection tank. It is ideal for interior and exterior facilities maintenance contractors who need to collect wash water or for restoration contractors who need to pick up large volumes of water after a fire or flood. Increase your efficiency with optional vacuum tools or even a Twister Vacuum that can be used with Hydro Tek recovery vacuums. (For use with cold water or hot water up to 200°F)

Looking for a high powered dry/shop vacuum? Add the optional dry work filter and vacuum accessories to your RPV and you have an incredibly high powered dry vacuum. Ideal for a building service contractor or a professional auto detailer.

- Model# RPV30E1 - Recover and transfer 30gpm  
115v, 15amp or 3500w generator
- Model# RPV50E1 - Recover and transfer 50gpm  
115v, 20amp or 5500w generator



Optional portability available: Choose either a caster wheel kit or a dolly style wheel kit

See additional wastewater solutions in the Hydro Vacuum® product line at <http://www.hydrotek.us/recycle.htm>

# WATER RECOVERY ACCESSORIES


Protecting storm drains from wash water run-off is important to mobile wash contractors. Using berms is the simplest way redirect wastewater. To contain and recover the wash water, arrange sand tube berms (available in 2', 6', 10') and place a vacuum scupper attachment or Hydro Vacuum Arch (#ATP40) to vacuum the water run-off.




Hydro Vacuum Arch  
Part# ATP40



2' gutter berms,  
# ZMAT2 & scupper



Scupper, #ZMAT6 10' berm,  
& #ZMAT7 6' deluxe berm



For larger containment needs, use a 12' x 25' wash pad (ZBPAD). Foam filled sides contain the water. Wash pad sets up in 3 minutes and is light enough to fold up, store and move to the next job.



Turn your pressure washer into a **sludge, slurry or water evacuation tool**. Pressure energy of spray from pressure washer wand creates suction that pulls water, up to 87gpm, through a heavy wall discharge hose. The Hydro Tek muck scupper connects to existing 1/4" pressure washer wand quick connect coupler, no other tools required. Ideal for clean out of sump pits, draining a fountain or pond, and flood cleanup. (#ANS04 or ANS55)

▶▶▶ See all these accessories in action at: [www.hydrotek.us/accessories.htm](http://www.hydrotek.us/accessories.htm)  
DISTRIBUTED BY:

**HYDRO TEK**  
CLEANING EQUIPMENT MFG.  
2353 Almond Ave. Redlands, CA 92374  
phone 800.274.9376 or 1.909.799.9222  
[www.hydrotek.us](http://www.hydrotek.us) fax 909.799.9888



Lynco Products Inc  
# 114, 1220 - 28 STREET N.E.  
CALGARY, AB T2A 6A2  
403-250-3600 / 1-877-249-3600  
[sales@lynco.com](mailto:sales@lynco.com) / [www.lynco.com](http://www.lynco.com)